

need to comment on
3.2.3

Appendix A. **Opinion of Probable Costs**

Description	Summary Items	Comments
Slurry Seal, Type II-PMCS-1h-EAS, (15bs/sy, 1/4", 18% asphalt emulsion), parking lot	3.2.4: Repair, patch, coat, and stripe parking surfaces.	This item is scheduled for completion in 2027 as a part of normal maintenance. Seal Coat was completed four years ago.
Clearing & grubbing, heavy trees, to 24" diameter, cut and chip	3.2.6: Cut back trees and vegetation from building.	Landscapers have been directed to provide additional pruning in the next 30 days. This is normal maintenance.
Hose bib, 3/4", brass	3.2.8.1: Repair/replace hose bibs(s).	Plumber has been contacted to make repair.
Backflow preventer, double check principle, corrosion resistant, automatic operation	3.2.8.1: Repair backflow preventer leaks.	Plumber has been contacted to make repair.
Light fixtures, residential, outdoor, PAR floodlights, 2 lamp, each, 150 W	3.2.8.2: Repair/replace damaged exterior lights and outlets.	Electrician has been contacted to make repair.
Wood framing, heavy mill timber, columns, structural grade, 1500f, 8" x 8"	3.3.2: Replace damaged support posts.	This is common on the Island. Working with contract to secure bid. Work will be done within the next 90 days.
Rotary / reciprocating refrigerant compressors, refrigeration, hermetic, switches and protective	3.3.2/3.8.1/7.3: Replace walk-in cooler compressor, keg cooler, and repair main walk-in cooler.	Tenant responsibility. Tenant will be notified.
Subfloors, plywood, CDX, 3/4" thick	3.3.2/3.7.3: Replace termite damaged and moisture damaged attic sheathing and stairs landing.	This work has already been bid and a contract is in place to complete.
Wood framing, heavy mill timber, beams, built from 4" lumber, multiple 4" x 8"	3.3.3: Repair bridge framing, enclosure, railing, and beams.	Working with contract to secure bid. Work will be done within the next 90 days. This is common on the Island.
1-line pipe rail with attached handrail, steel, primed, 1-1/2" pipe	3.3.3: Replace damaged railing, balconies, and enclosures.	Working with contract to secure bid. Work will be done within the next 90 days. This is common on the Island.
Wood product siding, plywood, Texture 1-11, cedar, factory stained, 5/8" thick	3.3.3: Replace moisture/termite damaged siding rafter tails, soffits, and purlins.	Working with contract to secure bid. Work will be done within the next 90 days. Much of this was repaired eight years ago during a major remodel.
Stair, shop fabricated, steel, 4'-0" W, incl picket railing, stringers, metal pan treads, excl concrete for pan treads	3.3.3.1: Repair stairs and balcony decking.	Work already contracted for and in progress.
Doors, solid wood, six panel, pine, 1-3/4" thick stile and rail, 3'-6" x 8'-0"	3.3.3.1/7.2: Replace termite damaged, framing, and trim. This includes replacing broken fixed window panes.	Working with contract to secure bid. Work will be done within the next 90 days.
PVC louvers, movable blades, commercial grade, 36" x 36"	3.3.3.1: Replace worn gabled vent louvers with vinyl louvers.	Work already contracted for and in progress.
Steel roofing panels, on steel frame, corrugated or ribbed, galvanized, 24 gauge	3.3.4: Repair worn/damaged roofing, flashing, flat roofing materials, penetrations, and gutters.	Property was painted eight years ago as part of a major remodel. It is scheduled again in two years.
Pipe, cast iron soil, one hub, service weight, 4" diameter, lead and oakum joints 10' OC, includes	3.4.1.1: Clear and repair drain, waste, and vent plumbing pipes and drains.	Plumber has been contacted to make repair.
Pipe, copper, tubing, solder, 3/4" diameter, type L, includes coupling & clevis hanger assembly 10' OC	3.4.1.2: Repair water heater overflow pipe.	Tenant responsibility. Tenant will be notified.
Water heater, electric, point of use, glass lined, energy saver, single element, 2.5 gallon	3.4.1.2: Replace point of use water heater.	Tenant responsibility. Tenant will be notified.
Split ductless system, cooling only, single zone, wall mount, 2 ton cooling	3.4.3.1: Replace worn HVAC equipment.	Tenant responsibility. Tenant will be notified.
Metal ductwork, fabricated rectangular, galvanized steel	3.4.3.2: Clean and repair ventilation ducting and registers.	Tenant responsibility. Tenant will be notified.
Sprinkler system components, connector for sprinkler heads, 60" length, 1/2" and 3/4" outlet size	3.4.4.1/3.6.1: Relocate sprinkler pipe from main electrical enclosure. This includes replacing corroded riser supports.	Fire Sprinkler company contacted to complete repair.
Panelboards, 3 phase 4 wire, main lugs, 120/208 V, 100 amp, 24 circuits	3.4.4.2: Repair electrical panels, junction boxes, and electrical defects in this section of the report.	Electrician has been contacted to make repair.
Hydraulic passenger elevators, for 2,000 lb. capacity, add	3.5: Service, inspect, and load test elevator. This includes rekeying lock.	State has been non responsive to our requests due to limited staffing.
Fire extinguishers, dry chemical, pressurized, standard type, portable, painted, 10 lb.	3.6.3: Replace expired/missing extinguishers.	Work will be completed in the next 30 days.
Emergency lighting units, lead battery operated, twin sealed beam light, 25 W, 6 V each	3.6.4: Replace inoperable emergency lights.	Electrician has been contacted to make repair.
Repair and renovate interior tenant spaces.	3.7.3: Repair and renovate interior tenant spaces. This includes repair of interior tenant non-bathroom spaces.	Tenant responsibility. Tenant will be notified.
Water closet, tank type, vitreous China, floor mounted, close coupled, two piece, includes seat, Faucets/fittings, sink, faucets	3.7.6: Repair out of service toilets.	Tenant responsibility. Tenant will be notified.
	3.7.6: Repair bathroom faucet.	Tenant responsibility. Tenant will be notified.
Cooler, commercial kitchen equipment, reach-in, beverage, 6' long	3.8.1: Replace bar equipment.	Tenant responsibility. Tenant will be notified.
Fans, roof exhauster, centrifugal, aluminum housing	3.8.2: Remove and dispose of roof-mounted vent equipment.	Tenant responsibility. Tenant will be notified.
Insulation, insulated protectors (ADA), for exposed piping under sinks or lavatories, vinyl coated foam, Velcro tabs, p trap, 1-1/4" or 1-1/2"	4.1: Install/repair ADA p-trap pads.	Tenant responsibility. Tenant will be notified.

part

al

and

d

already

Continue to follow up.

has been